BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/BD/WORK_INDENT13908

APPROVED SCHEDULE - B

No. E/BTP/BBMP/E-PMT/07/2014-15, Date: 31.10.2014

construction of Ranga Mandhira building in ward no. 10 (Doddabommasandra), Vidyaraynapura sub division.

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of R MADHUSUDAN	
				In Figures	In Words
1	130	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking	Cum	221.42	Rupees Two Hundred Twenty One and Forty Two Paise Only
2	98.85	Providing and laying in position plain cement concrete of mix M 7.5 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4169.27	Rupees Four Thousand One Hundred Sixty Nine and Twenty Seven Paise Only
3	43.2	Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing with new stones etc complete as per specifications and directions of engineer in charge of the work	Cum	5156.75	Rupees Five Thousand One Hundred Fifty Six and Seventy Five Paise Only
4	24.3	Providing and laying in position plain cement concrete of mix M 15 withOPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	Cum	4643.6	Rupees Four Thousand Six Hundred Forty Three and Sixty Paise Only
5	288	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	77.66	Rupees Seventy Seven and Sixty Six Paise Only
6	4.91	Providing and laying cement concrete using 20mm and down size granite course aggregates and fine aggregates of ready mixed concrete for R.C.C works laid in 15cms thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3,with all lead and lift etc., complete. (exclusive of cost of steel and fabrication charges) Ready mixed cement concrete for Beams, column, Staircase and Roof with M-20(cement -320 Kg/Cum) etc complete as per specifications and directions of engineer in charge of the work	Cum	6284.86	Rupees Six Thousand Two Hundred Eighty Four and Eighty Six Paise Only

Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

7	5.4	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications.Specification No. KBS 4.6.3 -do- for TMT Bars Fe 415 etc complete as per specifications and directions of engineer in charge of the work	qtl	7171.6	Rupees Seven Thousand One Hundred Seventy One and Sixty Paise Only
8	158.4	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for columns, pillars, piers, post and struts, circular or curved in plan including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	827.98	Rupees Eight Hundred Twenty Seven and Ninety Eight Paise Only
9	196	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1 m in depth including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	237.16	Rupees Two Hundred Thirty Seven and Sixteen Paise Only
10	546	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for stairs (excluding landing) except spiral staircase including cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work	sqm	455.44	Rupees Four Hundred Fifty Five and Forty Four Paise Only
11	3100	Fabricating supplying and erecting M.S. TubulerTruss of span upto 10m bottom and top member is provided with 50x50x6mm double equale angles, welded back to back and in between top and bottom line, in ereas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided all the members are weldeded togeher with 6mm gusset plate as per drawing, Nos CBS/SD/K- mantap/9/MND/97. The enter truss is anchored in RCC column buy using 4Nos of M.S anchor bolts at eacth support, with 10mm thick base plate and shoe plate. The work includes cutting, straightening , pacing in position of M.S angle and welding wherever necessary, and applying one of red oxide primer coat to all the members including cost of all materials, labour charges,and higher charges of mechineries for cutting welding, granding and erection equipments, etc complete as per specifications and directions of engineer in charge of the work	kgs	123.83	Rupees One Hundred Twenty Three and Eighty Three Paise Only
12	235.9	Providing Meta color sheet roofing with J or L hooks, bolts and nuts 8mm dia C.I plain and bitumen washers over the existing purlins, rafters and trusses includeing cost of materials, labour, etc complete as per specifications and directions of engineer in charge of the work	sqm	1188	Rupees One Thousand One Hundred Eighty Eight Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92